## HASSAN DIVISION.

*The 5th April* 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to end of April 1897, for making certain alterations and additions to the Taluk Cutcherry at Belur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 A. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for making certain alterations and additions to the Taluk Cutcherry at Belur;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Hassan division, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

MAKING ALTERATIONS AND ADDITIONS TO THE TALUK CUTCHERRY AT BELUR.

| *Items.* | *Quantities.* | |
|---|---|---|
| Excavating foundations | 78 | C. yds. |
| Fort stone in chunam | 1,977 | C. ft. |
| Burnt brick in chunam | 4,557 | ,, |
| Arch work | 28 | ,, |
| Plastering with mortar | 49·53 | Sqrs. |
| Burnt stone slabs | 204 | S. ft. |
| Do | 132 | ,, |
| Cornice work | 198 | R. ft. |
| Teakwood work wrought and put up | 204·37 | C. ft. |
| Roofing with 1st class Mangalore tiles and teak reepers, &c. | 18·33 | Sqrs. |
| Roofing with corrugated zinc sheets | 13·24 | ,, |
| White and color washing | 49·53 | ,, |
| Red painting to doors and windows | 4·00 | ,, |
| Removing and re-fixing old windows | No. 5 | .. |
| Do do old doors | No. 3 | .. |
| Flooring with Mangalore tiles | 84·0 | Sqrs. |
| Flooring with gravel | 9 | C. yds. |
| Burnt stone slab flooring with asphalte joints | 6·60 | Sqrs. |
| Dismantling and removing old roof | Lump sum. | |
| Do do Bengal terrace | Lump sum. | |
| Teakwood doors | 250 | S. ft. |
| Do windows with double shutters | 68 | ,, |
| Do ventilators | 6 | .. |
| Cealing with honnewood planks | 505 | Sq. ft. |
| Bamboo matting | 7·43 | Sqrs. |
| Wood oiling | 22·60 | ,, |
| Dismantling walls | Lump sum. | |
| Removing rubbish | Lump sum. | |

A. S. NAGAVKAR, *Executive Engineer.*

## BANGALORE CITY MUNICIPALITY.

*Notification, dated 7th April* 1897.

Notice is hereby given that a sum of Rs. 3-3-2, being the sale proceeds of the undermentioned property, belonging to the deceased Sivaiya of the City Incurable Ward, is held in deposit at the City Municipal office. All persons claiming the said amount are requested to attend during office hours either in person or by their representatives and prove their title thereto to the satisfaction of the President within six months from date of first publication of this notice in the *Mysore Gazette*, after which date no claims will be heard and the above amount will be credited to Municipal Funds.

*Description of property.*

One pair gold earrings, 1 brass chamboo, 1 brass banie small, 1 pair of scissors, 1 cup, 1 tin box, 1 coat, 1 waist coat, 1 bag, 3 old pancheys and cash Re. 0-9-3.

*Note*:—The clothes were burnt.